

HDR Remodeling

Information Sheet

Wires & Cable Installations/Repairs

HDR accepts no responsibility for a performance of the computer wire. We will follow the specifications of the customer and will insure that the transfer wire will be free of any kinks or breaks. Other than that HDR accepts no responsibility. HDR will follow current codes for running low voltage lighting power lines and telephone lines. Customer agrees to hold HDR harmless for any work done on computers.

1. HDR will drill a 1/2" or better hole through the floor in a mutually agreed spot in the home and will staple the cable using plastic ended staples. The staples will be a minimum of 24" on center and will be more than 36" from any heat-producing product such as a heater etc.
2. HDR will protect the cable using 1/2" schedule 40 PVC or Plastic EMT under the house to a point that the cable exists the house through a stucco wall. The opening in the stucco wall will be sealed with caulk to keep water out. This price does not include painting the stucco patch the color of the house.
3. The cable will be run under the steps and will drop a minimum of 8" below grade and will be protected in schedule 40 PVC or in plastic EMT.
4. The cable will be run in this manner for approx. 40 feet on the left side of the cement sidewalk.
5. A hole will be blasted under the sidewalk using or water blaster or similar method. The cable will be run through the hole in a manner described in #2.
6. The cable will then be routed up against the cottage and into to a interface box that will then allow the wire into the cottage on the back side away from the back on the main house.

All standard terms and conditions apply.